



## Utilities West Corridor Overview

### RTD Utility Coordination Role

- Coordinate with utility companies to identify and locate all existing utilities
- Identify all utility relocations required by the corridor project
- Coordinate with all utility owners on the design of relocating their utilities
- Meet with utility owners to discuss and resolve utility challenges and issues
- Identify roles and responsibility for relocating existing utilities and financial responsibility
- Negotiate and sign utility relocation agreements with the utility owners
- Write work orders to initiate design and construction of relocations of existing utilities
- Approve relocation design for compatibility with the project and inspect utility relocations during construction
- Identify and coordinate utility relocations constructed by the utility owners that will take place prior to the corridor construction
- Survey and stake pertinent proposed construction features such as ROW, storm sewer pipes, manholes and signal gate foundations
- Coordinate survey and documentation on the corridor design drawings of relocated utilities that cross under the LRT guide way
- Keep the RTD public involvement group informed on the upcoming utility work

### RTD Corridor Construction Contractor role

- Coordinate utility relocations during corridor construction
- Construct all wet utilities such as sewer and water lines with the exception of facilities owned by Consolidated Mutual Water Company and the Sanitary Relocation Project that will be constructed by the City of Lakewood (13<sup>th</sup> Avenue Balsam to Harlan)